BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41613

APPROVED SCHEDULE - B

SE

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work: Improvements to roads & drains of byregowda layout in ward no.07 Byataranapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KIRAN GOWDA D (SRI CHANNAKESHAWA ENTERPRISES)	
				In Figures	In Words
1	272.7	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	Cum	116.03	Rupees One Hundred Sixteen and Three Paise Only
2	37.62	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	4635.75	Rupees Four Thousand Six Hundred Thirty Five and Seventy Five Paise Only
3	77.22	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.878 cum and fine aggragtes @ 0.53cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	Cum	4839.24	Rupees Four Thousand Eight Hundred Thirty Nine and Twenty Four Paise Only
4	4.25	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	60899.32	Rupees Sixty Thousand Eight Hundred Ninety Nine and Thirty Two Paise Only
5	633.6	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.	Sqm	406.99	Rupees Four Hundred Six and Ninety Nine Paise Only
6	200.25	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	1967.75	Rupees One Thousand Nine Hundred Sixty Seven and Seventy Five Paise Only
7	590	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x150x500 mm and finished with CM 1:3 plastering and finishing cutting etc., complete	Nos	393.6	Rupees Three Hundred Ninety Three and Sixty Paise Only
8	265.5	Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte	Sqm	33.02	Rupees Thirty Three and Two Paise Only
9	24	Laying Reinforced cement concrete pipe NP2 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls	Mtr	5032.03	Rupees Five Thousand Thirty Two and Three Paise Only
10	2.26	Providing 100mm and down size nominal size.	Cum	831.58	Rupees Eight Hundred Thirty One and Fifty Eight Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KIRAN GOWDA D (SRI CHANNAKESHAWA ENTERPRISES)	
				In Figures	In Words
11	0.9	Providing 40mm and down size nominal size	Cum	918.98	Rupees Nine Hundred Eighteen and Ninety Eight
12	0.9	Providing 20mm and down size nominal size	Cum	918.98	Rupees Nine Hundred Eighteen and Ninety Eight Paise Only
13	0.68	Providing Fine aggrgate 2.36mm nominal size	Cum	887.71	Rupees Eight Hundred Eighty Seven and Seventy One Paise Only
14	16	Providing and fixing MS Grating 260x260 mm	Nos	75.65	Rupees Seventy Five and Sixty Five Paise Only
15	272.7	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	79.43	Rupees Seventy Nine and Forty Three Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92